



1. 4 BUD FLOURESCENT SURFACE MOUNT FIXTURES, 10-15 CUMTS
2. OFF WHITE EPOXY COATING-ALL WALLS
3. ENTIRE CEILING AREA PAINTED DARK CHOCOLATE GRAY (FLAT) ENAMEL
4. RELOCATE 1 1/2" GAS LINE FRO ENTER-CEILING GENERATOR
5. INSTALL 2" DIA. "GALV" "HEXUSTYLE" TIE-ROD THRU THIS AREA
6. ACCENT COLOR WALLS TO BE SELECTED BY STAFF ARCHITECT AT TIME OF CONSTRUCTION
7. ATTENDANTS DESK IS OPTIONAL

1. CERAMIC TILE ALL WALLS & FLOOR
2. CERAMIC TILE SPLASH GUARD IN CENTER OF ROOM
3. EPOXY COATED CEILING WITH VAPOR PROOF FLOURESCENT FIXTURES (B)
4. EXHAUST SPACE TO EXTERIOR OF
5. ELEVATE FLOOR NO MORE THAN 4"

1. TREAT WALLS, FLOOR AND CEILING AS IN AREA 'A'
2. WATER COOLER INSTALLED IN THIS AREA

REV	DATE	APPD.	DESCRIPTION		BY
PROJECT NO.		PROJECT TITLE			
		<u>AVES BLDG. GYMNASIUM</u> <u>& SHOWER/LOCKER ROOM</u> SCALE _____ $\frac{1}{8"} = 1'-0"$			
SHEET TITLE					
<u>PROJECT PLAN & GENERAL NOTES</u>					
DRAWN BY	DATE	TRACED BY	DATE	CHECKED BY	DATE
DD	8/9/72				
APPROVED BY		SHEET		FILE NO.	
_____		OF			